BRUHAT BANGALORE MAHANAGARA PALIKE

BBMP/2014-15/OW/WORK_INDENT16464

APPROVED SCHEDULE - B

No.EE/BTP/BBMP/E-PMT/07/2014-15, Date: 31.10.2014

Name of Work: Maintenance of BBMP Drilled Borewells in Ward No. 09, Vidyaranyapura Sub Division.

Sl. No.	Approved Qty.	Description	Unit	Approved Tender Rates of Bharath Adithya V	
				In Figures	In Words
1	30	Lifting of Submersible pump set as per Soecification and direction etc., complete and as per the directions of the Engineer-in-charge of the work	No.	892.08	Rupees Eight Hundred Ninety Two and Eight Paise Only
2	30	Transportation of pumping machineries etc., complete and as per the directions of the Engineer-in-charge of the work	No.	892.08	Rupees Eight Hundred Ninety Two and Eight Paise Only
3	30	Labour charges (over hauling) etc., complete and as per the directions of the Engineer-in-charge of the work	No.	577.23	Rupees Five Hundred Seventy Seven and Twenty Three Paise Only
4	10	**A) Repairs to Motor:** Rewinding of submersible pump sets with copper insulation wire of suitable gauge as per ISI specification with guarantee of 6 months. etc., complete and as per the directions of the Engineer-in-charge of the work **A) 10 HP Motor**	No.	3883.15	Rupees Three Thousand Eight Hundred Eighty Three and Fifteen Paise Only
5	20	**B) 12.5 HP Motor**		4985.13	Rupees Four Thousand Nine Hundred Eighty Five and Thirteen Paise Only
6	30	Starter (with one year Guarantee) etc., complete and as per the directions of the Engineer-in-charge of the work	No.	5299.98	Rupees Five Thousand Two Hundred Ninety Nine and Ninety Eight Paise Only
7	30	Rotor (with one year Guarantee) etc., complete and as per the directions of the Engineer-in-charge of the work	No.	4932.65	Rupees Four Thousand Nine Hundred Thirty Two and Sixty Five Paise Only
8	30	Upper Flange etc., complete and as per the directions of the Engineer-in-charge of the work	No.	367.33	Rupees Three Hundred Sixty Seven and Thirty Three Paise Only
9	30	Lower Housing etc., complete and as per the directions of the Engineer-in-charge of the work	No.	682.18	Rupees Six Hundred Eighty Two and Eighteen Paise Only
10	30	Carbon Housing etc., complete and as per the directions of the Engineer-in-charge of the work	No.	498.51	Rupees Four Hundred Ninety Eight and Fifty One Paise Only
11	30	Thrust bearing block assembly complete with Segment bearing pad.etc., complete and as per the directions of the Engineer-in-charge of the work	No.	1206.93	Rupees One Thousand Two Hundred Six and Ninety Three Paise Only
12	30	**C) Replacement of pump parts:** The following main components of submersible pump sets requiring replacement. Oil Seal etc., complete and as per the directions of the Engineer-in-charge of the work	No.	131.19	Rupees One Hundred Thirty One and Nineteen Paise Only
13	30	Oil Seal Steel Bush etc., complete and as per the directions of the Engineer-in-charge of the work	No.	157.43	Rupees One Hundred Fifty Seven and Forty Three Paise Only
14	450	Guide vane etc., complete and as per the directions of the Engineer-in-charge of the work	No.	183.66	Rupees One Hundred Eighty Three and Sixty Six Paise Only

15	450	Impeller Shell moulded with aluminium Bronze) etc., complete and as per the directions of the Engineer-in-charge of the work	No.	446.04	Rupees Four Hundred Forty Six and Four Paise Only
16	30	Discharge outlet (D.O) Bearing D.O Steel Bush etc., complete and as per the directions of the Engineer-in-charge of the work	No.	467.04	Rupees Four Hundred Sixty Seven and Four Paise Only
17	30	Steel Bush etc., complete and as per the directions of the Engineer-in-charge of the work	No.	157.43	Rupees One Hundred Fifty Seven and Forty Three Paise Only
18	30	Pump shaft made out of stainless steel Centreless ground with key way (upto 8 stages) etc., complete and as per the directions of the Engineer-in-charge of the work	No.	997.03	Rupees Nine Hundred Ninety Seven and Three Paise Only
19	30	Non – return valve (NRV) assembly complete with rubber 'O' Ring etc., complete and as per the directions of the Engineer-in-charge of the work	No.	1416.83	Rupees One Thousand Four Hundred Sixteen and Eighty Three Paise Only
20	30	Cable Guard etc., complete and as per the directions of the Engineer-in-charge of the work	No.	157.43	Rupees One Hundred Fifty Seven and Forty Three Paise Only
21	30	Brass Filter etc., complete and as per the directions of the Engineer-in-charge of the work	No.	262.38	Rupees Two Hundred Sixty Two and Thirty Eight Paise Only
22	30	Re-erection charges of pumping machineries including overhauling and pointing etc., complete and as per the directions of the Engineer-in-charge of the work	Each	997.03	Rupees Nine Hundred Ninety Seven and Three Paise Only
23	145	Supplying and drawing 3 core flat PVC sheathed submersible pump cable manufactured with electrolytic grade copper with flexible copper conductor confirming to table 3 class 5 of IS:8130-1984 and virgin grade PVC insulation and sheathed suitable for working voltage upto 1100 Volts. P. No. 49/ I No. 29-b(1) **4 Sqm mm of 56 strands 0.3mm dia Group - A** etc., complete and as per the directions of the Engineer-in-charge of the work	Mtr	158.47	Rupees One Hundred Fifty Eight and Forty Seven Paise Only

Bharath Adithya

Signature of the Contractor

Executive Engineer
Byarayanapura Division
BBMP, Bangalore - 92